LINE DATA		
LINE	BEARING	DISTANCE
L50	N 85°03'36" E	29.76'
L51	N 87°23'00" E	47.74'
L52	S 84°46'57" E	48.75'
L53	S 70°09'59" E	42.12'
L54	S 54°52'08" E	42.69'
L55	S 36°43'06" E	41.12'
L56	S 22°58'32" E	43.63'
L57	S 14°58'33" E	47.61'
L58	S 14°01'55" E	48.70'
L59	S 13°39'03" E	49.88'
L60	S 13°40'17" E	50.13'
L61	S 13°59'10" E	49.99'
L62	S 13°45'48" E	49.99'
L63	S 13°40'45" E	49.72'
L64	S 12°42'14" E	49.06'
L65	S 10°09'29" E	18.09'
L66	S 53°42'33" W	23.80'
L67	S 32°13'15" W	40.95'

LINETYPE LEGEND:

COMBINATION SILT & TREE PROTECTION FENCE (STAGE 1)	
TREE PROTECTION FENCE (STAGE 1)	
LIMIT OF DISTURBANCE (STAGE 1)	
COMBINATION SILT & TREE PROTECTION FENCE (STAGE 2)	
TREE PROTECTION FENCE (STAGE 2)	
LIMIT OF DISTURBANCE (STAGE 2)	
PRIVACY FENCE	—x—x—x—x—x—x—

TOWN OF APEX REQUIRED PLAN NOTES:

1. NO SITE DEVELOPMENT ACTIVITY INCLUDING, BUT NOT LIMITED TO, TESTING, CLEARING, INSTALLATION OF S&E MEASURES, OR GRADING, SHALL OCCUR UNTIL REQUIRED TREE PROTECTION FENCING HAS BEEN INSALLED AND INSPECTED. A TREE PROTECTION FENCING INSTALLATION PERMIT MAY BE OBTAINED AT THE PLAANING DEPARTMENT OR ONLINE AT http://www.apexnc.org/215/Applications-Schedules
2. TREE PROTECTION FENCING MUST BE PLACED:
   A) ONE FOOT AWAY FROM ANY SAVED TREE FOR EACH INCH OF DIAMATER AT BREAST HEIGHT
   B) ALONG THE OUTSIDE LINE OF THE 100-YEAR FLOODPLAIN, AND THE OUTSIDE EDGE OF ANY RIPARIAN BUFFER, AND
   C) AT LEAST 10 FEET AWAY FROM ANY OTHER DESIGNATED RCA SUCH AS, BUT NOT LIMITED TO, HISTORIC BUILDINGS AND STRUCTURES, WETLANDS, AND PONDS.
3. ADDITIONAL TREE PROTECTION FENCING MAY BE REQUIRED IN OTHER LOCATIONS CLOSE TO CONSTRUCTION ACTIVITY WHERE IT IS DEEMED NECESSARY BY THE ZONING ENFORCEMENT OFFICER; SUCH AREAS MAY INCLUDE BUT ARE NOT LIMITED TO COMMON PROPERTY LINES OR NEAR PUBLIC AREAS (SIDEWALKS, ETC.)
4. IF BUILDINGS ARE TO BE DEMOLISHED, A COPY OF THE DEMOLITION NOTIFICATION FROM THE NC HEALTH HAZARD CONTROL UNIT AND AN ASBESTOS INSPECTION REPORT FROM A NC ACCREDITED ASBESTOS INSPECTOR MUST ACCOMPANY THE APPLICATION FOR THE DEMOLITION PERMIT WHICH MUST BE OBTAINED PRIOR TO START OF THE DEMOLITION.

NOTES:

1. ALL MATERIALS AND METHODS OF CONSTRUCTION SHALL BE IN ACCORDANCE WITH TOWN OF APEX STANDARDS AND SPECIFICATIONS.
2. BOUNDARY & EXISTING CONDITIONS INFORMATION TAKEN FROM A SURVEY BY BARRY SCOTT LAND SURVEYORS.
3. TOPOGRAPHIC INFORMATION TAKEN FROM A SURVEY BY BARRY SCOTT LAND SURVEYORS, AND BLENDED WITH TOWN OF APEX LIDAR INFORMATION.
4. PER FEMA MAP #3720071000L (DATED JULY 19, 2022), NO 100-YR FLOODPLAIN EXISTS WITHIN THIS PROJECT.
5. THE SITE WAS REVIEWED FOR ENVIRONMENTAL FEATURES BY TERRACON CONSULTANTS, INC. THE WAKE COUNTY PROJECT NUMBER IS WC-23-003.
6. THIS SITE IS LOCATED WITHIN THE PRIMARY WATERSHED PROTECTION OVERLAY DISTRICT AND IS WITHIN THE JORDAN LAKE PROTECTED AREA.
7. ANY EXISTING STRUCTURES WILL ALL BE REMOVED. ANY EXISTING WELLS AND SEPTIC TANKS WILL BE ABANDONED ACCORDING TO WAKE COUNTY HEALTH DEPARTMENT STANDARDS.
8. BEFORE DEMOLITION OF EXISTING STRUCTURES/SITE FEATURES SUCH AS FENCING ARE IMPLEMENTED, THE TREE PROTECTION FENCING IS TO BE PERMITTED, INSTALLED AND INSPECTED PRIOR TO ANY OF THE DEMOLITION WORK. IF THERE ARE EXISTING TREES IN THE BUFFERS WHERE THE FENCING WILL BE REMOVED, FENCING IS TO BE REMOVED BY HAND.
9. A DEMOLITION PERMIT WILL BE REQUIRED PRIOR TO DEMOLITION OF ANY STRUCTURE. A LETTER OF ASBESTOS ABATEMENT WILL NEED TO ACCOMPANY THE APPLICATION FOR PERMIT. A LETTER OF ASBESTOS REMOVAL WILL BE REQUIRED PRIOR TO PERMIT ISSUANCE.
10. NO MACHINERY OF ANY KIND IS ALLOWED BEHIND THE TREE PROTECTION FENCE (TPF). ANY ITEMS SHOWN BEHIND TPF THAT MUST BE REMOVED (EX. ELECTRIC POLES, ELECTRICAL LINES, SMALL BUILDINGS, TRASH, ETC) SHALL BE REMOVED BY HAND OR USING MACHINES STATIONED OUTSIDE THE TPF.

0 25 50 100
GRAPHIC SCALE

THE SIGNATURES AFFIXED BELOW CERTIFY THAT THIS SHEET HAS BEEN REVIEWED AND APPROVED SOLELY PER THE CERTIFICATIONS SIGNED ON THE COVER SHEET OF THESE CONSTRUCTION PLANS.

Approved rdalton 11/20/2024 3:01:26 PM TRANSPORTATION ENGINEERING N / A sawarna 11/21/2024 9:30:31 AM	DATE	Approved WR - STORMWATER & S&EC N / A smayo 11/18/2024 4:49:16 PM	DATE
BUILDING INSPECTIONS N / A smiller 11/20/2024 6:54:18 AM		PLANNING N / A jmeder 11/20/2024 10:00:44 AM	
WR - UTILITY ENGINEERING N / A jharris 11/21/2024 11:14:39 AM	DATE	PLANNING - TRANSPORTATION N / A bhampton 11/21/2024 10:02:56 AM	DATE
ELECTRIC N / A tgarrington 11/20/2024 2:46:03 PM	DATE	FIRE	DATE
PARKS, RECREATION & CULTURAL RES.	DATE		

Jones & Chossen
ENGINEERING, PLLC
Civil Engineering | Construction Management | Land Planning

221 N. SALEM ST.
SUITE 001
PO BOX 1062
APEX, NC 27502
Office: 919-387-1174
Registration: P-0151
www.jonescnossen.com

NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 049836 PATRICK L KIERNAN 11/21/24

ASHLAND
CONSTRUCTION DRAWINGS
WAKE COUNTY, NORTH CAROLINA

STAGING & DEMOLITION PLAN

TOWN OF APEX

SCALE 1"=50'	DRAWN PLK
DATE MAY 1, 2024	

REVISION	
7/5/24	PER TRC
9/10/24	APPROVAL SET
10/16/24	EX. CENTERLINE
10/31/24	SEWER OUTFALL A
11/12/24	STAGE 2 SILT FENCE

SHEET 12

PROJECT 2326